


## ADDENDUM TO THE CONTRACT DOCUMENTS

	ADDENDUM NO. 003
	Project: Solano Community College District <b>Pool Deck Replacement Project</b> Project Number: 23-006
	Date: March 8 <sup>th</sup> , 2023

**Addendum No. 003 – The following clarifications are provided and must be added/considered when completing your bid:** Acknowledgement of receipt of this **Addendum No. 003**, is required on the Bid Form. Please clearly note the addendum date and number.

### **ITEM NO. 1 – GENERAL INFORMATION**

- 1.1.** Swimming Pool Concrete – Specification Section 13 11 02
- Replace Section 3.4.C.1 with the following;  
Contractor shall provide three (3) mock-up deck samples, minimum 8'x 8', each. The cost of this mock-ups shall be included in bid. This mock-up should be standalone and include concrete deck, tile, tooled expansion joints, linear pool slot/trench drain, flush mounted deck boxes, rebar, pool edge, wedge anchors. etc. These (3) mock-up samples shall be constructed; one (1) with a light broom finish, one (1) with a medium broom finish and one (1) with a heavy broom finish for determination and selection of an appropriate deck finish. Each mock-up sample shall be edged on all four sides to demonstrate a 3/4" radius edge. Anchor installation shall demonstrate acceptable interface between anchor and the top of deck. The contractor shall provide everything required to receive the desired quality with the mock-up. The approved mock-up will be used as a point of reference during the project to ensure quality of the project. The contractor will not be allowed to start the final deck until the quality of the finish work has been approved by the District. These mockups shall be removed and disposed by the contractor upon the completion of the project.

### **ITEM NO. 2 – DRAWINGS**

- 2.1.** *None*

**ITEM NO. 3 – RESPONSES TO QUESTIONS SUBMITTED**

**3.1.** *None*

**List of Attachments:**

- *None*

END OF DOCUMENT